SKYLARK APARTMENTS AT KHARAR PUNJAB

LDC No: 66/16

Licence issued vide Memo No. LDC-1646/DPC dated 16-11-06 (Within Municipal Limits of Kharar) (3.145 ACRE SCHEME) AS ON 31.12.2005

4079

COVERED AREA STATEMENT :-

S.No.	FLOORS	BLOCK -1 (SHOPS / OFFICES / RESIDENCE)		BLOCK -2 (SHOPS / OFFICES / RESIDENCE)		BLOCK -3 (SHOPS / OFFICES / RESIDENCE)		BLOCK -4 (SHOPS / OFFICES / RESIDENCE)		TOTAL		REMARKS
		FREE OF F.A.R.	UNDER F.A.R.	FREE OF F.A.R.	UNDER F.A.R.	FREE OF F.A.R.	UNDER F.A.R.	FREE OF F.A.R.	UNDER F.A.R.	FREE OF F.A.R.	UNDER F.A.R.	
		V	VI	VII	VIII	IX	X	XI	XII	XIII	XIV	XV
1.	BASEMENT	NIL	NIL	NIL	NIL	NIL	NIL	NIL	NIL	NIL	NIL	
2.	GROUND FLOOR	10,855.00 (903.00)	10,855.00 (903.00)	5,720.39 (476.00)	NIL	NIL	NIL	NIL	NIL	27,293.39	NIL	
3.	FIRST FLOOR	1,292.92 (108.00)	3,230.00 (269.00)	2,388.19 (199.00)	1,203.13 (100.00)	NIL	NIL	1,203.13 (100.00)	1,203.13 (100.00)	3,161.63	3,774.11	
4.	SECOND FLOOR	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	3,161.63	33,492.41	
5.	THIRD FLOOR	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	3,161.63	33,492.41	
6.	FOURTH FLOOR	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	3,161.63	33,492.41	
7.	FIFTH FLOOR	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	3,161.63	33,492.41	
8.	SIXTH FLOOR	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	1,292.92 (108.00)	12,096.22 (1,007.00)	3,161.63	33,492.41	
	GRAND TOTAL	19,682.00	74,965.51	15,660.00	72,583.90	14,837.17	NIL	12,270.64	72,583.90	50,346.04	2,00,838.83	
											346.65 % OF PLOT AREA	

PARKING AREA CALCULATIONS:

A. RESIDENTIAL

1.	TOTAL SALEABLE AREA ON ALL THE FLOORS (REFER FAR CHART)	=2,00,838.83 sqft. = 18,665.32 sqmt.
2.	PARKING AREA REQUIRED AS /PRESCRIBED NORMS	= 33,783.41 sqft. = 3,139.72 sqmt.
	i) 10 % of the gross area of the site i.e. 1,30,995.345 sqft.	= 13,099.53 sqft
	ii) 10 % of covered area on all the floors i.e. 2,00,838.83 sqft.	= 20,083.88 sqft
3.	PARKING AREA ACTUALLY PROVIDED	= 34,871.51 sqft. = 3,240.85 sqmt.
	a) COVERED PARKING = 33,431.51 sqft.	
	i) UNDER STILTS = 27,703.38 sqft.	
	ii) UNDER SHED = 5,728.13 sqft.	
	b) OPEN PARKING = 1,440.00 sqft.	
	in FRONT OF COMMUNITY CENTRE 96'-0" X 15'-0" = 1,440.00 sqft.	

INFERENCE PARKING AREA PROVIDED IS MORE THAN ADEQUATE (103.22 % OF THE MINIMUM PRESCRIBED) SUFFICIENT TO PARK 100 CARS, 125 TWO WHEELERS & 50 CYCLES HENCE SAFE W.R.T. CURRENT NEEDS GENERATED BY SOCIO ECONOMIC FORCES

TWO BED ROOM UNIT BLOCK

COVERED AREA STATEMENT ON TYPICAL FLOOR

S.NO.	PARTICULARS	NO.	SIZE	AREA (in sft)
1	BLOCK 3	01	33'-0" X 22'-3" - 6'-10" X 5'-0" =726.72 - 34.50 =692.22 SQ.FT.	6,164.34
	AREA UNDER PROJECTIONS / BALCONIES			
2	BLOCK 3	01	2'-1" X 5'-0" X 6 =6 X 11'-6" X 4'-6" =3 X 11'-6" X 4'-0" =3 X 10'-3" X 2'-9" = 24.8"X10" =216.11 SQ.FT.	1210.11

AREA UNDER ORGANISED PARKS / GREEN STRIPS

S.NO.	PARTICULARS	SIZE:	AREA (sqyds)	
A	AREA UNDER PARKS			
1.	PARK - I	52'-0" x 243'-0" + 51'-3" x 112'-0"	1,501.78	
2.	PARK - II	52'-0" x 136'-3"	844.86	
	TOTAL AREA UNDER PARKS		2,346.64 sqyds	(15.42%)
B	AREA UNDER GREEN STRIPS			
3	G.S. I		291.00	
	TOTAL AREA UNDER G. STRIPS		291.00 sqyds.	(1.91%)
	TOTAL AREA (A+B)		2637.64 sqyds	(17.33%)

ACTUAL GROUND COVERAGE

1	SALEABLE AREA =			9,563.14 sft
	A) RESIDENTIAL (Covered area)		6437.51	
	i) OTHER BED ROOM IN BHK BLOCK "1 & 2" = 4 (76.38sft			
	a) Stairs / lifts = 2x(24.0+24.0+8") = 116.38			
	b) EWD = 2x8x10.0+5.0+8'-6" = 494.00			
	ii) TWO BED ROOM BLOCK "3" = 1664.13 sft			
	a) Stairs / lifts = 3 X 16.6"x 16'-0" = 1012.48			
	b) EWS = 3x10'-5"x5'-0" = 636.25			
	B) SHOPS/ OFFICES & COMMUNITY CENTRE		3126.63 sft	
	i) BLOCK "4" = 36'-3" 86'-0" = 3135.63 sft			
2	AREA FREE OF FAR (STILTS)			23,929.27 sft
	A)RESIDENTIAL (Covered area)			
	i) 3BR BLOCK "1 & 2" = area on F. F. - saleable area on S.F. =(43.10.944.22 - 2388.19) = 19,416.06		23,929.27 sft	
	ii) 2 BR BLOCK "3" = area on F. F. - saleable area on S.F. = 6164.34 - 1664.13 = 4513.21			
	B) SHOPS/ OFFICES & COMMUNITY CENTRE		NIL	
	TOTAL		33,492.41 sft.	
	(9,563.14 + 23,929.27)			= 34,416.07 PLOT AREA

AREA STATEMENT

TOTAL AREA OF LAND		15,221.705 Sq.yds
i) 24 KANAL - 09½ MARLA = 14,807.375 (as per revenue record)		3.145 ACRE
ii) 00 KANAL - 13.997 MARLA = 414.33 (area of NAV ENCLAVE merged with SKYLARK apartments) (ref.: site plan for calculations)		1.273 HECTARE
MAXIMUM PERMISSIBLE COVD. AREA ON GROUND FLOOR (50 % OF PLOT AREA)		7,610.85 Sq.yds
ACTUAL AREA PROPOSED TO BE COVERED ON GROUND FLOOR		3,721.38 Sq.yds
A- RESIDENTIAL = 3,372.98 SQYDS		(24.45%)
B- COMMUNITY FACILITIES = 348.40 SQYDS (COUNTED IN FAR)		
AREA UNDER PUBLIC AMENITIES		11,500.325 Sq.yds (75.55%)
Parks, organised green spaces/strips & Swimming pool = 2,891.84 SQYDS	(18.99%)	
Water Works	NIL (0.00%)	
Electrical Sub Station	75.61 SQYDS (0.50%)	
Sewage T. Plant	NIL (0.00%)	
Roads & open common parking = 8,533.875 SQYDS	(56.06%)	
MAXIMUM PERMISSIBLE COVD. AREA ON ALL THE FLOORS WITH FAR = 2.0 (15,221.705 x5 x 2.0)		2,73,990.69 Sq.ft
ACTUAL COVD. AREA ON ALL FLOORS EXCLUDING AREA FREE OF FAR i.e. STILTS/ PROJECTIONS ETC. (9,563.14 x 1 +33,492.41 x 2 + 33,220.53 x 1 + 30,356.78 x 3) (REFER DETAILED AREA STATEMENT CHARTS)		2,00,838.83 Sq.ft (1.466 < 2.0)
PERMISSIBLE F.A.R.		2.00
ACTUAL F.A.R. =		1.466
NO. OF DWELLING UNITS 1 BR TOWER = 3 X 48 = 144 2 BR TOWER = 3 X 4 = 12 TOTAL = 3 X 51 = 153		151
MAXIMUM POPULATION @ 5 person per D.Unit (151 x 5)		755
MAXIMUM PERMISSIBLE DENSITY OF D.UNITS/ACRE (48 + 40 + 40 = 5		60.00
ACTUAL DENSITY OF D.UNITS/ACRE (151 / 3.145)		48.01
MAXIMUM PERMISSIBLE DENSITY OF POPULATION (PERSONS/ ACRE)		300.00
ACTUAL DENSITY OF POPULATION (PERSONS / ACRE) (755 / 3.145)		240

REVISIONS

S.NO.	DATE	PARTICULARS
1	8/10/06	12'-0" WIDE SETBACK PROVIDED BETWEEN THE WIDE OF ADDITIONAL COMMUNITY BLOCK-4 AND THE NAV ENCLAVE WALL FACING NAV ENCLAVE ON EASTERN SIDE AS DESIRED BY THE COMPETENT AUTHORITY IN THE MEETING ON 04/10/06

PROMOTERS | ARCHITECT | COMP.AUTHORITY

for Skylark Housing Construction Pvt. Ltd. Kuldeep Singh Director

(Surya Kant)

Competent Authority Senior Town Planner B.D.A. Patiala

kant and associates

1307/sgtb complex, sector - 70, sas nagar -160070 (chandigarh)
tel:0172-2270327, fax :0172- 2270325, website :www.kantassociates.com
email : skant@sify.com, skant@kantassociates.com

CONSULTING ARCHITECTS, INTERIOR DESIGNERS, URBAN DESIGNERS, LANDSCAPE ARCHITECTS, ENVIRONMENT DESIGNERS AND PLANNERS

CORPORATION DRAWING

LAYOUT PLAN AND AREA STATEMENT

SCALE	PROJECT	DRAWING NO.
1" = 32'-0"	ka cd 0702	02

CONCEPT	DESIGN	DEALT	DRAWN	CHECKED	DATE
S.KANT	S.KANT	ANJU	RAVI	S.KANT	19072006

COPY RIGHT :

This drawing and design is a copy right. It is loaned for the project mentioned above in the title of this sheet and, is subject to recall at any stage.It shall not be lent,copied,traced,altered,reproduced or used in whole or in parts without the written permission of the proprietor.



LAYOUT PLAN